

BID SCHEDULE

CITY OF RIVIERA BEACH

REQUEST FOR PROPOSAL NO. 950-18-3

CITY OF RIVIERA BEACH MARINA - SUPPLY OF FIXED AND FLOATING DOCKS - PIERS E, F and G

PAGE 1

Marinetek North America Inc

RESPONDENT

NO	DESCRIPTION	QUANT	UNIT	UNIT PRICE	TOTAL LINE ITEM BID AMOUNT
Pier E - Fixed and Floating Dock Systems - Base Bid					
1	8' Wide Fixed Aluminum Pier - Delivered to the site with installation hardware.	1,472.0	SF	\$85.00	\$125,120.00
2	Aluminum Finger Pier (6'x56')- Floating with Integrated Ramp System - Delivered to the site. (2) 20" pile guides with installation hardware.	2.0	EA	28,560.00	\$57,120.00
3	Aluminum Finger Pier (8'x76')- Floating with Integrated Ramp System - Delivered to the site. (3) 20" pile guides with installation hardware.	1.0	EA	\$51,680.00	\$51,680.00
4	Cleats - 15" (5-Ton Min.) - Furnish Only	22.0	EA	\$100.00	\$2,200.00
5	5-Step Aluminum Ladders - Furnish Only	3.0	EA	\$525.00	\$1,575.00
Total Pier E - Fixed and Floating Dock Systems					\$237,695.00

NO	DESCRIPTION	QUANT	UNIT	UNIT PRICE	TOTAL LINE ITEM BID AMOUNT
Pier F - Fixed and Floating Dock Systems - Base Bid					
6	14' Wide Floating Concrete Wave Attenuator - Delivered to the site - Concrete float system with integral concrete deck, utility troughs, (17) 24" pile guides and installation hardware.	4,550.0	SF	\$155.00	\$705,250.00
7	14' Wide Fixed Aluminum Pier with Triangular Transition (overlay of existing pier) - Delivered to the site with aluminum supports and installation hardware.	2,433.0	SF	\$85.00	\$206,805.00
8	8'-9" Wide Fixed Aluminum Pier (overlay of existing pier) - Delivered to the site with aluminum supports and installation hardware.	1,589.0	SF	\$85.00	\$135,065.00
9	Aluminum Finger Pier (6'x46')- Floating with Integrated Ramp System - Delivered to the site. (2) 20" pile guides with installation hardware.	1.0	EA	\$23,460.00	\$23,460.00
10	14' Wide Fixed Aluminum Gangway Access Pier - Delivered to the site with aluminum supports and installation hardware.	644.0	SF	\$85.00	\$54,740.00
11	6' x 40' Aluminum Gangway - Delivered to the site with installation hardware.	1.0	EA	\$25,200.00	\$25,200.00
12	Cleats - 20-Ton Bollard - Furnish Only	4.0	EA	\$2,500.00	\$10,000.00
13	Cleats - 10-Ton Bollard - Furnish Only	18.0	EA	\$750.00	\$13,500.00
14	Cleats - 15" (5-Ton Min.) - Furnish Only	8.0	EA	\$100.00	\$800.00
15	5-Step Aluminum Ladders - Furnish Only	6.0	EA	\$525.00	\$3,150.00
Total Pier F - Fixed and Floating Dock Systems					\$1,177,970.00

**BID SCHEDULE
CITY OF RIVIERA BEACH
REQUEST FOR PROPOSAL NO. 950-18-3
CITY OF RIVIERA BEACH MARINA - SUPPLY OF FIXED AND FLOATING DOCKS - PIERS E, F and G
PAGE 2**

**Marinetek North America Inc
RESPONDENT**

NO	DESCRIPTION	QUANT	UNIT	UNIT PRICE	TOTAL LINE ITEM BID AMOUNT
Pier G - Floating Dock System - Base Bid					
16	14' Wide Floating Concrete Wave Attenuator - Delivered to the Site - Concrete float system with integral concrete deck, utility troughs, (16) 24" pile guides and installation hardware.	4,830.0	SF	\$155.00	\$748,650.00
17	12' Wide Floating Concrete Wave Attenuator - Delivered to the Site - Concrete float system with integral concrete deck, utility troughs, (2) 24" pile guides and installation hardware.	480.0	SF	\$155.00	\$74,400.00
18	5'-6" Wide Floating Concrete Finger Piers - Delivered to the Site - Concrete float system with integral concrete deck, triangular braces, (1) exterior 20" pile guide and installation hardware.	6.0	EA	\$25,000.00	\$150,000.00
19	Cleats - 20-Ton Bollard - Furnish and Install	4.0	EA	\$2,500.00	\$10,000.00
20	Cleats - 10-Ton Bollard - Furnish and Install	6.0	EA	\$750.00	\$4,500.00
21	Cleats - 5-Ton - Furnish and Install	57.0	EA	\$100.00	\$5,700.00
22	5-Step Aluminum Ladders - Furnish and Install	6.0	EA	\$525.00	\$3,150.00
Total Pier G - Floating Dock System					\$996,400.00

Total Base Bid - Piers E, F and G:

\$2,412,065.00

Total Base Bid in Writing: Two Million, Four Hundred Twelve Thousand, Sixty-Five

Add / Deduct Bid Items

NO	DESCRIPTION	UNIT PRICE	UNIT
23	Internal Pile Guide 24" Steel Pipe Pile - Furnish & Install (HDG)	\$2,500.00	EA
24	External Pile Guide 24" Steel Pipe Pile - Furnish & Install (HDG)	\$3,500.0	EA
25	Internal Pile Guide 20" Steel Pipe Pile - Furnish & Install (HDG)	\$2,250.00	EA
26	External Pile Guide 20" Steel Pipe Pile - Furnish & Install (HDG)	\$3,250.00	EA
27	Cost to Meet Warranty Criteria - If Applicable	Included	EA
28	Cost for Annual Inspections and Maintenance	Included	YEAR

BID SCHEDULE**CITY OF RIVIERA BEACH****REQUEST FOR PROPOSAL NO. 950-18-3****CITY OF RIVIERA BEACH MARINA - SUPPLY OF FIXED AND FLOATING DOCKS - PIERS E, F and G****PAGE 3**

Marinetek North America Inc

RESPONDENT**Alternate Bid Items**

NO	DESCRIPTION	UNIT PRICE	UNIT
29	5' Wide Aluminum Frame Finger Piers - Delivered to the Site - Aluminum frame with concrete floatation , hardwood decking, triangular braces, pile guides and installation hardware.	\$19,500.00	EA
30	5' Wide Aluminum Frame Finger Piers - Delivered to the Site - Aluminum frame with polyethylene floatation , hardwood decking, triangular braces, pile guides and installation	\$17,000.00	EA
31	Internal pile guides for 20" steel pipe piles fabricated using all stainless steel components, including frame members, roller brackets, roller pins and hardware.	\$4,250.00	EA
32	External pile guides for 20" steel pipe piles fabricated using all stainless steel components, including frame members, roller brackets, roller pins and hardware.	\$5,250.00	EA
33	Internal pile guides for 24" steel pipe piles fabricated using all stainless steel components, including frame members, roller brackets, roller pins and hardware.	\$4,500.00	EA
34	External pile guides for 24" steel pipe piles fabricated using all stainless steel components, including frame members, roller brackets, roller pins and hardware.	\$5,500.00	EA

Bid schedule has been prepared to include major components of work.

It shall be the Respondent's responsibility to review plans and specifications and to bid accordingly.

All square foot numbers pertaining to floating docks are approximate.