Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

We are pleased to offer this quote for the Broadway Center Fountain. We are providing proposal for the design intent.

Fountain will be designed as commercial water feature, with a complete control system. Includes bright white LED lights. Electric auto fill system, filtration system, and finishes. We design all our systems to be both user friendly, and as maintenance free as possible. Equipment designs to include a, control panel and timing system. Fountain design, and Finishes included in design specifications withstanding owner approval.

Note that through the design and engineering process there may be modifications to the equipment listed, and layout in the subsequent quote.

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

Shop Drawings (electronic sets)
Design Package for Fountain Includes:

Cover page
Site plan Page
Hydraulics Design
Structural Design
Elevation Page
Electrical Layout
Equipment pages

Engineering Stamped and sealed

Equipment:

Aluminum Door	qty. 1
Control Panel System	qty. 1
LED light controller	qty. 1
Low voltage power supply	qty. 2
Control panel box	qty. 1
Feature pump starter	qty. 2
System breakers	qty. 6
Level sensor control system	qty. 1
Solenoid power supply	qty. 1
Low level shut off	qty. 1
Feature pump timer	qty. 1
Lights timer	qty. 1
Feature pumps	
15 Hp 3 phase(inline centrifugal)	qty. 1
Approx. 30 ln ft feature water wall	
Required GPM 600 @ 60’ TDH	
TECO VFD drive	qty. 1

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

Filter pump	
1HP Pentair Whisperflo filter pump	qty. 1
Cartridge filter	
Modular Media Cartridge Filter 200 Sq Ft	qty. 1
Equip. Room fan	qty. 1
Inline chlorinator Rainbow 320	qty. 1
Eye Ball filter returns black	qty. 6
Side wall vacuum	qty. 1
Discharge manifolds	qty. 3
Sch 80 unions	qty. 2
Suction manifolds	qty. 2
2” 3 way filtration suction valve	qty. 2
2” 2 way discharge valve	qty. 3
Butterfly valves 8”	qty. 1
Butterfly valves 6”	qty. 1
Butterfly valves 4”	qty. 2
Discharge rock screen diverter	qty. 2
Skimmer side wall	qty. 2
Level sensor auto fill float	qty. 1
Side wall overflow	qty. 1
Floor drain 3” Brass	qty. 1
Stainless Steel fountain lights	
12v-24v DC bright white	
Ring Lights	qty. 6
Waterwall lights	qty. 15
Underwater J-Box Stainless steel	qty. 5
3M re-interable potting compound	qty. 5
Stainless Steel Floor penetrations 1.5”	qty. 6
Stainless Steel Floor penetrations .75”	qty. 5
Main drain Sumps Grates 12”x 24”	qty. 2.

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

Construction:

- Hydraulic install
- Equipment install
- Rebar #3 12" O.C.E.W. (or/as per engineering)
- CMU block walls (equipment room only)
- Sump Main drains
- Concrete Forms
- Concrete Shell 10" walls
  - 4000 psi pump mix
- Waterproofing Basecrete taped seems on any cold joints
  - All interior floors and walls (Black Color)
- Precast coping 14" x 4'
- Water wall gunite shoot at proper water wall angle

.

Finishes:

- Water wall tile (allowance $15 sq. ft.)
- Water line tile (allowance $15 sq. ft.)
- Below basin waterline, & floors Basecrete
- Wall coping (color TBD)
  - 13" x 4" x 4' textured semi rough
- Exterior stucco and paint by others

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

Quote Includes:

- Excavation for hydraulics
- Setting vault
- Construction of Fountain Forms
- Steel as per shop drawings specifications
- Hydraulic trenching
- Hydraulics between vault and fountain Max. Sch. 40
- Installation of all fountain equipment
- Supply and Installation of all fountain finishes
- Electric between equipment and fountain panel
- Installation of fountain lighting
- Start up
- Turnover

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

Owner to provide

- Drain where applicable
- 1" waterline hook up to refill
- Drain to equipment room/fountain
- Access to site via working trucks
- Fill dirt or dirt removal
- Electric supply to Vault Control panel
- Electrical permits
- Concrete demolition or removal
- All signage

Total Cost: $428,000.00

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

TERMS AND CONDITIONS OF THE SALE

1) This quotation is subject to our Standard Terms and Conditions of the Sale, and is valid for thirty **(30) days**. This quotation is very general. The actual material(s)or layout may be subject to change once it is reviewed through the design/engineering process for the total Scope of Work to be complete.

2) Crystal Waterscapes, requires a 50% deposit on equipment payable upon issuance of Purchase Order from Client, with the balance due before delivery of the goods. Crystal Waterscapes, Inc. shall not have any obligation to commence manufacturing of any Purchase Order and further reserves the right to stop manufacturing and processing of any Purchase Order unless or until such deposit is paid.

3) All fountain components must be **PAID IN FULL** before leaving the United States.

4) The required deposit will release a work order for shop drawings (PDF Format) to begin, and be delivered in a reasonable time

5) Any delay in payment of the deposit will delay delivery of the products or result in termination of the Purchase Order.

6) Cancellation of orders received by Crystal Waterscapes, Inc. will result in the loss of the deposit.

7) All components returned are subject to a restocking charge and must have an RMA number authorized from Crystal Waterscapes,

8) It is the Purchaser's responsibility to inform Crystal Waterscapes of shipping schedules. Once these schedules have been established, you are obligated to receive the shipment of this product.

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

9) **STORAGE -** If a scheduled ship date is delayed, Crystal Waterscapes. can store the finished goods, but payment for these finished goods shall be paid to Crystal Waterscapes. Space will be on a project-to-project basis as space is very limited.

10) We have found it not practical to itemize the many miscellaneous supplies and materials used on each project. To do so would considerably add to our costs and labor charges.

11) It is the Buyer's responsibility to keep Crystal Waterscapes updated with the latest editions of drawings or changes pertaining to Crystal Waterscapes Scope of Work

12) **INSURANCE –** Crystal Waterscapes will furnish our standard Certificate of Insurance if required for the purchase of materials or services. Liability supplied before mobilization to job site. If additional insurance is requested, an extra fee will be added to the purchase price.

13) **PROMOTION –** Crystal Waterscapes reserves the right to Photograph, Film and/or Video our workmanship and product for on-site documentation and for use in promotional materials including, but not limited to, Printed Collateral, Advertisements, Multimedia, Internet and CD/DVD-ROMs.

Crystal Waterscapes
Fountains, Falls, & Features
6615 Sable Ridge Ln
Naples FL. 34109
239-253-0444

Job: Broadway Fountain
Date: 2/03/2020
Quote #200203

• Acceptance According To Crystal Waterscapes Terms, Conditions and Bid Documents •

If the previously listed proposal and terms are acceptable to you please sign below and return to Crystal Waterscapes by Email Robert@CrystalWaterscapes.com

Accepted this _____ day of _____, 2020.

Accepted by (print name):_____ of

_____(signature):_____.
Co. Name

Quote By Robert Engler
President Crystal Waterscapes (A DBA of Robert Engler Const. Co. Inc.)
Florida Certified Contractor License # 1456678